

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 24. NR. 14 W.

Manistee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 27 and 34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap,  
6" below surface

WITNESSES TO CORNER

18" Cherry - N57E - 96½ links

6" Maple - S50E - 75½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Found part of stove rail at corner, probably as established in local survey by proportion. Reset iron 2 links east to conform to midpoint, on line, between Section corners. Government BTs all gone.

Corner was placed and witnessed August 21, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*  
REGISTERED LAND SURVEYOR

DATE 12/27/60