

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 . NR. 14 W . .

Manistee

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 27-28-33-34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap, 6" below surface

WITNESSES TO CORNER

Power pole - N39E - 114 1/2 links

Apple tree - S15W - 107 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this township. Found small strap iron in centerline of roads north, south, east, west, and southwest. Checks fence line measurements in mile north, and was apparently used in the prior establishment of the 1/4 corner east. No government evidence. Appears to be acceptable as best available evidence of corner.

Corner was placed and witnessed August 21, 1960

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 12/27/60