

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24. NR. 14 W.

Manistee

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 26-27-34-35

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap,
6" below surface

WITNESSES TO CORNER

8" Maple - S7E - 112½ links

12" B. Cherry - S57W - 166 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this township. Found ½x2" angle iron in place in center of road, probably as established by E.W. Muenscher in 1915 for highway commission. Evidence of fence post witness north 23', with evidence of old fence going north. No evidence of original Cedar and Ash witnesses, since this area is high upland with Beech, Maple and Cherry cover. Although this corner appears to be somewhat north of a more desirable position based on measurements north and south, it does seem to ~~WARRANT~~ warrant consideration on the basis of its priority, its use in controlling road alignment, its acceptance in other possible surveys in this section, and in the absence of government evidence to the contrary.

Corner was set and witnessed August 21, 1960.

SURVEYORS SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 12/27/60