

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 23 NR 13 W  
T 23 NR 14 W  
T 24 NR 13 W  
T 24 NR 14 W  
----- Manistee ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 1-6-31-36

DESCRIPTION OF CORNER MONUMENT Left 1" pipe in place, set 1/2" iron bar over pipe to surface.

WITNESSES TO CORNER -----

6" Elm - N5E - 58 links  
-----  
18" Elm - N51W - 102 1/2 links  
-----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in T24NR14W. Found 1" pipe in place in center of E-W county road at intersection with old RR grade NE-SW. A very old Cedar NBT NE. Government BTs all gone, but corner seems acceptable as best evidence of township corner.

Corner was witnessed May 2, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 5/6/60  
REGISTERED LAND SURVEYOR