

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 24 N.R. 14 W
T. 24 NR 15 W
Manistee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 30-31-25-36

CORNER MONUMENT 1" pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/21/61

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

6" Cedar	-	N76E	-	32.3 feet
8" Maple	-	N1W	-	27.6 feet
AND 7" Elm	-	S6W	-	28.4 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a survey in this area. Set corner from probable NBT noted by county surveyor in 1912 survey, a 24" W. Pine stump, the only one within 50 links. Checks for line and measurement over corners south which is how it was set in 1912 when no US corner could be found. Also checks stream crossing south and swamp edge north. Considered this best available evidence of proper location for corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 9/25/61
REGISTERED LAND SURVEYOR