

Mawstee Co. ✓

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 14 XX W.	E-3 E-4 E-5
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 7-14-1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-3 Reestablished corner in approximately the center of "T" road intersection (E-W-N) in line with fence to South. Corner fits previous surveys of record.
- E-4 Recovered large stone in N-S fence remains per deceased County Surveyor Jas. Millard. See page 179 of White Co. Survey Book at Reg. of Deeds.
- E-5 Corner restored from Bill Batzer's (RLS) Witness and County Road Commission witness.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3			E-4			E-5		
Set	Std.	Dept. Mon	Set	Std.	DNR Monument	Set	3/4" x 30" pipe	
		buried 0.5'						
18"	Maple	S43E 31.30'	5"	Maple	N01W 31.7'	6"	R. Pine	N 8E 114.85'
7"	tw.Maple	N17E 64.69'	6"	Maple	N68E 19.7'		Power Pole	N16E 66.72'
9"	tw.Maple	N38W 59.20'	8"	Maple	S15W 36.4'		C.Line b.top rd Due N	9.6'
Fen.corner	Due S	23'					6" R. Pine	N60E 115.00'


SIGNED BY Carl F. Roser DATE 12-4-72

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____