

MAWISLEE Co. ✓

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. <del>XX</del> R. 14 <del>XX</del> W.	F-4 D-3
2. PROPERTY CONTROLLING IN SECTION	Sec 9, T. 24 N. <del>XX</del> R. 14 <del>XX</del> W.	8
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 7-14 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-4 Ctr. of Sec. 9, inaccessible, established computationally per Std. B.L.M. instructions. See Witness corners below. (Item C).
- D-3 Accepted corner as recovered and re-monumented by Bill Batzer, RLS, Traverse City.
- Code 8 Established West 1/16 corner on E-W 1/4 line (inaccessible) computationally per Std. B.L.M. instructions. See Wit. Corner below. (Item C).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<i>Wit. Cor. to Ctr. of Sec. 9</i> F-4: Set. Cor. #2 1"x36" pipe & Ced Post 3" Cedar clmp N13W 31.7' 3" Cedar clmp N60W 32.0' 9" Cedar S52W 35.4' W bank of Rv. Due E 7'± Ctr of Sec 9 inaccessible N87°44'E 21.7'	<i>Wit. Cor. to Ctr. of Sec. 9</i> F-4: Wit Cor. #1 Fd. 4" rd con. monument 11" Cedar S18W 59.7' 10" Cedar S10E 49.0' 9" Cedar N82E 37.6' Ctr. Sec. 9 inaccessible N00°16'W 231.0'	D-3: Found 1" pipe 9" Maple N51W 39.4' 9" trpl Map, N57E 67.2' 8" Maple S47W 47.9' CODE 8: Set 1"x36" pipe, post & loc. tag. 8" Cedar S33E 24.6' 5" Cedar S10W 26.7' W 1/16 cor on E-W line N87°44'E 76.0'
--	---	---


SIGNED BY Carl F. Roser DATE 12-4-72

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_