

Manesteg Co v

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>24</u> N. <u>xx</u> , R. <u>14</u> E. <u>x</u> W.	F-3 G-4 G-5
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S., R. _____ E. _____ W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S., R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 7-13 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-3 Recovered corner per recorded plat of "Old Grade Crossing".
- G-4 Corner restored per recorded plat of "Old Grade Crossing".
- G-5 Accepted 3/8" spike in blacktop road. Fits recorded plat of "Old Grade Crossing".

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 4" rd con. mon.	Set 4"x36" Con.Mon w/Cons cap.	Fd. 3/8" spike in b.top rd
7" R. Pine N 5E 50.46'	9" Maple Twin N20E 60.62'	9" Cherry S62W 89.32'
Power Pole N84E 52.90'	16" B. Cherry S66W 65.17'	6" Cherry N10W 61.20'
8" R. Pine S60W 79.75'	14" B Cherry twin S10W 87.28'	Power Pole N74E 112.37'
		Ctr E-W b.top rd Due N 1'


SIGNED BY Carl F. Roser DATE 12-4-72

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_