

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>24</u> N. <u>14</u> R. <u>14</u> W.	D-7; E-8; <u>E-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 11, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- D-7 Restored S 1/4 Cor., Sec. 17, on line between the SW & SE Cor's. of S-17 and at prorated distance, W 1/2 mile J.H. Millard (1881-1901), E 1/2 mile U.S. (1839). This method of restoration fits J.H. Millard's numbers for split of Sec. 17 for Ctr. of section, very reasonable.
- E-8 Fd. and accepted 1" pipe by RLS, Tony Slawinski; Cert. Sur., Liber 1, Pg. 50, June 1972. Corner is in Ctr. of N-S trail road.
- E-9 Accepted SE Cor. of Sec. 20 per RLS, Glenn DeLaMater survey of Sec. 28; Certificate Survey for Shell Oil Co., job No. 741086.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-7	E-8	E-9
Set DNR Mon. & Ced. Post.	Fd. 1" Pipe (buried 0.5').	Fd. 3/8" pipe w/RLS Cap.
6" W. Pine S57°W 131.2	5" Maple (Clp. of 4)	6" W. Pine S13°W 46.46
30" W. Pine Stp. N27°E 73.2	S88°E 32.35	R. Pine S63°E 87.69
Telephone Cable Riser post S77°E 99.81	*18" Maple N28°E 35.66	10" Cherry N10°W 34.18
Ctr. E-W dirt co. Rd. Due S 36'+	*11" Cherry (clp. of 3) S52°W 39.67	Set Ced. Post w/Loc. Tag N01°24'E 33'
	*equals same Wit. as T. Slawinski	Fd. Dept. Mon (buried) N62°13'W 2.1'

SIGNED BY Carl F. Roser 2-26-79 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SPRINGDALE TOWNSHIP  
MANISTEE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_