

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD


T. 24 N.R. 14 W  
T 24 NR 15 W Manistee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 18-19-13-24

CORNER MONUMENT Set 1"x24" pipe under stone, below surface

DATE MONUMENT PLACED AND WITNESSED 8/21/61

WITNESSES TO CORNER.....



|         |   |      |   |           |
|---------|---|------|---|-----------|
| 30" Elm | - | S27E | - | 32.0 feet |
| 10" Elm | - | S54W | - | 51.0 feet |

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in T24NR14W. Found large stone at corner which, according to county survey records, was placed at government post by local resident Ellis Humphrey in 1882. Corner was recovered by W.D. Manchester in 1926 and NBTs noted. Manchester's 16" Elm SE is still in place, now about 30" diam. His NW NBT gone. Considered this a proper restoration of the government corner.

SURVEYOR'S SEAL

SIGNED

*Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 9/25/61