

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24. NR. 14 W. .

----- Manistee ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 34 and 35
on South boundary of township

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER -----

6" Tamarack - N30E - 43½ links

6" Cedar - N17W - 40½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this township. Found very old stake point at corner and 2 NETs, probably established by Manchester in the early 1900s. One possible government BT in place. Checks acceptably with probable course of stream east and south.

Closing corner to Sections 2 and 3, T23N, R14W is 30 links west.

Corner was set and witnessed January 7, 1960.

SURVEYORS SEAL

SIGNED Kenneth Ostling DATE 1/8/60
REGISTERED LAND SURVEYOR