

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 14 W.	C-10
2. PROPERTY CONTROLLING IN SECTION 30	T. 24 N. R. 14 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION 30	T. 24 N. R. 14 W.	*723.4'-W of #1
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 11, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 11, 1978, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-10 — Re-estab. 1/4 Cor. equidistant between Sec. Corners 1/2 mile to N. & S. and on departure of 27'-E. of Rd. Ctr. Line (in curve) per W.D. Manchester records on this Corner dated March 5, 1942, large Co. Sur. Rec. Bk. A., Pg. 280. The Corner fits old ent. rd. to fish rearing ponds to E. & avg. line of Co. Rd. (now up-graded) that shows on 1938 Aerial Photos to West.
- 1 — Established 1/8 Corner (NE Cor. of E 1/2 of frl. W 1/2 of Fr1. NW 1/4 of Sec. 30) on line between Sec. Cor. to W. & 1/4 Cor. to E. and at pro-rated distance to original G.L.O. survey
- * — Established NW Corner of E 1/2 of frl. W 1/2 of frl. NW 1/4 of Sec. 30 equidistant and on line between NW Cor. S-30 and W 1/8 on N. line Sec. 30, (pro-rated to Orig. G.L.O. survey).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10	1	*
Set DNR Mon. & Ced. Post.	Drove 5/8"X40" re-rod	Drove 5/8"X40" re-rod w/Plastic
5" Maple N25°E 33.14	w/Plastic Cap & Cedar post	Cap & Ced. Post w/Loc. Tag.
12" R.Pine Due E 67.02	w/Loc. Tag.	13" Maple N77°E 25.7
8" R.Pine S30°E 70.64	8" Maple N56°E 42.9	20" Maple S64°E 28.8
Co. Rd. P.I. Set 5/8" re-rod	10" Maple S63°E 3.1	15" Maple S09°W 29.1
w/RLS Cap N00°22'22"E 118.17	12" Maple N45°W 21.9	E-W random Due N. 3.2
Ctr. B.Top Co. Rd. (in curve)	E-W random Due N. 3.0	
N'ly & SSW'ly-Due W 27'+		

SIGNED BY Carl F. Roser 2-26-79 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SPRINGDALE TOWNSHIP
 MANISTEE COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
 REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET