

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N. R. 14W


Manistee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 16-17-20-21

CORNER MONUMENT Set 1" pipe with aluminum cap, 6" below surface

DATE MONUMENT PLACED AND WITNESSED 11-2-61

WITNESSES TO CORNER.....



16" Twin Elm - N 33 E - 83.0 feet

5" Elm - S 54½ E - 51.0 feet

AND
8" Cherry - S 51 W - 69.6 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established in line with centerline of E-W county road at record measurement returned in surveys of Sections 21 by Millard and Manchester in early 1900's. Falls in line with old township road grade south, but could find no evidence of any previous corner, or new bearing trees. Best available evidence.

SURVEYOR'S SEAL

SIGNED *Harold J. Ostling* DATE 11/15/61
REGISTERED LAND SURVEYOR