

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 24 N. R. 14 W.	A-10; B-10
2. PROPERTY CONTROLLING IN SECTION 30	T. 24 N. R. 14 W.	8
3. MISCELLANEOUS PROPERTY IN SECTION 30	T. 24 N. R. 14 W.	XX = 720.7' E of A-10
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on March 25, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on March 25, 1980, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - Description of original monument and accessories and/or subsequent restoration:

C. (continued) XX
 Drove 5/8"x36" rerod w/RLS Cap
 7" Cedar S70°E 19.2
 12" Cedar S20°W 27.7
 9" Maple N30°E 54.1
 Set cedar post w/loc. tag North 33'
 Ctr. E-W dirt road North 8'±

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-10 Fd. & accepted iron rod for W¹/₄ corner Sec. 30. Corner is within one foot of being midway and on line between fd. section corners to N & S.
- B-10 Established center of Sec. 30 at intersection of ¹/₄ lines.
- 8 Established SW corner of E¹/₂ of frl. NW¹/₄ of Sec. 30 prorated to original GLO plat sub'n. of Sec. 30. Corner is S of ctr. of E-W dirt road at this point, but looking E'ly it is on approximate center of road.
- XX Established the SE corner of the W¹/₂ of W¹/₂ of NW frl. ¹/₄ of Sec. 30 equidistant & on line between the W¹/₄ corner & the W 1/8 corner on E-W ¹/₄ line as located prorated to GLO plat sub'n. of Sec. 30. (see survey file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10	B-10	8
Fd. ¹ / ₂ "x18" rod; replaced with ¹ / ₄ "x18" rod.	Drove 3/4"x18" solid iron rod	Drove 5/8"x36" rerod w/RLS Cap
6" Maple (in clmp) N35°W 42.92	10" Maple N10°E 55.3	9" Cedar S70°W 82.2
6" W. Pine S05°E 24.45	6" Twn. Maple N40°E 63.0	22" Maple S55°E 75.8
9" W. Pine N10°E 42.32	13" W. Pine S40°W 88.7	19" Maple N20°E 50.8
Set ced. post w/loc. tag North 33'	Set ced. post w/loc. tag North 33'	Set ced. post w/loc. tag North 33'
Ctr. E-W dirt road North 8'±	Ctr. E-W dirt road North 2'±	Ctr. E-W dirt road North 9'


SIGNED BY Carl F. Roser 7-23-80 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____
 SPRINGDALE TOWNSHIP
 MANISTEE COUNTY