

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 <sup>N.</sup> R. 14 <sup>W.</sup>	A-11; A-12
2. PROPERTY CONTROLLING IN SECTION 31	T. 24 <sup>N.</sup> R. 14 <sup>W.</sup>	3
3. MISCELLANEOUS PROPERTY IN SECTION	T. <sup>N.</sup> R. <sup>E.</sup>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 28, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-11 Fd. Dept. mon. as set in 1961 Dept. survey (corner was set from probable NBT, 24" W. Pine stump, as called for by Co. Surveyor in 1912. This fits line & meas. over corners S per 1912 survey & also checks stream crossing S & swamp edge N).
- A-12 Fd. & accepted iron for W $\frac{1}{4}$  S-31 as used & wit. by RLS J. Nelson (Mich. Cons. Gas Co.) #21273. Corner is in approx. ctr. of gravel road W & in line with b'top road looking south.
- 3 Established 1/8 corner per standard BIM instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11	A-12	3
Fd. DNR Mon.; added ced.post	Fd. 5/8" rerod w/RLS cap	Set 5/8"x36" rerod w/RLS
4" Maple N13 <sup>OW</sup> 6.73	#21273	Cap & ced.post w/loc.tag
14" Cedar N57 <sup>OE</sup> 60.85	10" Maple clstr.N09 <sup>OE</sup> 26.53	8" Maple N12 <sup>OE</sup> 21.5
*9" Cedar N81 <sup>OE</sup> 32.60	3" Maple N57 <sup>OE</sup> 41.85	5" Maple S35 <sup>OW</sup> 7.6
*10" Maple stub (5'high)	18" Maple S68 <sup>OW</sup> 55.33	6" Maple S66 <sup>OE</sup> 30.1
N04 <sup>OE</sup> 27.98	Set ced.post w/loc. tag	
*8" Dead Elm S10 <sup>OW</sup> 28.4	North 20'	
10' stream West 45'±		
10' stream South 250'±		
* = previous KJO or Nelson		
SIGNED BY _____ witnesses		

Carl F. Roser DATE 7-23-80



SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

SPRINGDALE TOWNSHIP  
MANISTEE COUNTY