

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Manistee

(County)

Located In: Corner Code ##

- 1. Public Land Survey T 24N R 14W C-07
T _____ R _____ (SE cor. Sec. 18)
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

REGISTER'S OFFICE
MANISTEE COUNTY

96-474 at 4:05pm

OCT 16 1996

Deborah Dix

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7			●										
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Bruce J. Jenema, in a field survey on September 5, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-07 SE corner of Section 18, T24N, R14W
- John Brink 1839 Deputy Surveyor Unrecorded LCRC 1978 Carl Roser
- 24" Hemlock for corner 17, 18, 19, 20 (5) 18" Elm stp. N44°E 93.40'
- (now extinct) (6) 17" W. Pine N10°W 142.30'
- 1881 J.H. Millard (7) MBT Cable riser N83°E 44.27'
- Found stump of corner tree & Cook's BT's (8) Fnd. 1" IP possible road PI
- (3) 12" Hemlock S48°E 13 links North 5.0'
- (4) 10" Lynn N71°W 33 links

Witnesses 3, 4, 5 & 7 are now extinct

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On Aug. 15, 1996, I found 5/8"x14" rod over a 12"x3/4" I.P. Also found 1" pipe for PI 5.00 ft. North from DNR drawing #78-6

Corner C-07 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Re-monument Act, MCL 54.261 et. seq.). Date of Peer Review: SEP 17 1996


Anthony M. Slavishi

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Aug. 15, 1996 I installed a Manistee County monument within a monument box in the exact location of the above 5/8x14" iron rod and is accepted as a careful and faithful re-establishment of the position of original corner and witnessed by:

- 6" Elm S43°E 65.49' 60-D W. side
- 12" Poplar N73°E 79.88' 60-D S. side
- MBT 4x4 N38°W 54.80' 60-D E. side
- (6) 30" W. Pine N10°W 142.30' DNR nail & tag W. side

Signed by *Bruce J. Jenema*
Surveyor's Michigan License No. 25850



Date Sept. 5, 1996