

JUL 03 2000

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Manistee _____ Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 24N R 14W D-13
 T _____ R _____ S 1/4 Sec 32
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REGISTER'S OFFICE
 MANISTEE COUNTY
 00-294 at 11:15 p.m.
 SEP 03 2000
Penny A. Pepera
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Anthony M. Slawinski, in a field survey on June 9, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- South 1/4 Corner Section 32 (24-14)
Set by John Brink in 1837.
- 1. Balsam 8" in dia. N 36 1/2° E 21 links (13.86')
- 2. Cedar 8" in dia. N 14 1/2° W 13 links (8.58')

Manistee County Surveyor's Record
 By Millard in 1913 in section 5 of T23N, R14W Book A, P196
 Map shows distances of closing corners, but does not state
 Monuments, or witnesses.

Survey Map for MOCO Production Company, By J.L. Wilcox & Associates in 1974.
 Set Iron Rod, Single Proportion against U.S. Government Survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

South 1/4 Corner Section 32 (24-14)
 On June, 2000, I, Anthony M. Slawinski along with a field crew from Abonmarche found a 5/8" iron rod in a monument box. We found no other evidence to dispute this location for the corner.

Condition of witnesses: #1 gone & #2 gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 1/4 Corner Section 32 (24-14)
 On June 9, 2000, I placed a Manistee County Monument, in a monument box in the exact location as the above mentioned 5/8" Iron rod as a careful and faithful re-established position of the original corner, and witnessed by:

- 3. N 42° E 42.59' 28" Twin Maple (found 60d in SE side of tree)
- 4. N 04° W 35.07' 12" Ash (set 60d in E side of tree)
- 5. S 39° W 43.40' 12" Ash (set 60d in N side of tree)
- 6. S 06° E 35.87' 10" Maple (set 60d in W side of tree)

Corner is in the centerline of 13 Mile Road. The North 1/4 corner of sec. 5 (23-14) is 19.18' to the West



Corner D - 13 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: 7-31-00

Anthony M. Slawinski

Signed by *Anthony M. Slawinski*
 Surveyor's Michigan License No. 13597

Date 7-26-00