

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Manistee  
(County)

Located In: Corner Code -#

- 1. Public Land Survey      T 24N R 14W      E-06 E $\frac{1}{4}$  Sec.17
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section               S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous           S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec.         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

REGISTER'S OFFICE  
MANISTEE COUNTY

96-471 at 3:50pm  
OCT 16 1996

*Deborah Six*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Bruce J. Jenema, in a field survey on September 5, 19 96

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-06 E 1/4 corner of Section 17, T24N, R14W  
John Brink 1839 Deputy Surveyor  
(1) 12" Beech for corner(now extinct)  
J.H Millard 1881  
(2) 30" Hemlock S82°W 17 links (now extinct)

2-26-1979  
Unrecorded LCRC Carl Roser  
Found Concrete monument  
(3) 6" S. Pine N05\*W 31.64'  
(4) 10" R. Pine N59\*E 82.38'  
(5) P.Pole S40\*E 45.45'  
(6) Concrete mon. South 32.97'

I did not locate witnesses 3,4, & 6

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On August 26,1996, I found concrete monument 4"x36" with a 1/2" rod in the center as the Northwest corner of Crystal Woods Subdivision.


Corner E-06 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1993, as amended, (being the State Survey and Reorganization Act, MCL 54.261 et seq.). Date of Peer Review: SEP 17 1995  
*Anthony M. Stannish*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On August 26,1996, I installed a Manistee County Monument in the exact location of the above monument and accepted as a careful & faithful re-establishment of the position of the original corner and witnessed by:

- (7) 15" R. Pine N65°E 65.56'
- (5) P. Pole S38°E 45.31' with DNR ID tag
- (8) 9" S. Pine N57°W 32.43'
- (9) 8" R. Maple N90°W 6.97'

Signed by *Bruce J. Jenema*  
Surveyor's Michigan License No. 25850



Date September 5, 1996

