

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee

(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|--|
| 1. Public Land Survey | T <u>24N</u> R <u>14W</u> | <u>F-5 (S¹/₄9)</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTER'S OFFICE
MANISTEE COUNTY

95-394 AT 1:43 p.m.
OCT 09 1995

Penny A. Pepera
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 30 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Bruce J. Jenema, in a field survey on September 11, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 9 & 16, established by John Brink on 8-11-1839 set 1/4 post and Witnessed by: Hemlock 14" S10°E 13 links Sugar 12" N17°W 21 links Book A, page 267, 1915 J.H. Mallard set cast sleigh shoe 25 links West of established fence line, Midway and on line between the SW and SE corners of Section 9

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

LCRC #73-4 Carl F. Roser Fnd 3/8 spike Found to fit recorded plat of Old Grade Crossing Witnessed by: [1] 12" Twin Maple S63°E 103.9' [2] 5" R. Pine S30°E 54.5' [3] Centerline E-W B. Top Road Due South 3.8' [4] concrete monument North 33.0' Found 3/8" dia. pipe with 3/8 spike in center; Found 3/8' dia pipe 0.72' East Further excavating this site in search for sleigh shoe and did not find

Corner E-85 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: October 3, 1995



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On Sept. 11, 1995, accepted 3/8" iron pipe and 3/8 spike of record As a careful and faithful re-establishment of the position of the original corner and installed a 2"x30" stainless steel pipe with a brass ID cap enclosed within a monument box and witnessed by:

- [1] 12" Twin soft Maple S63°E 104.2 Set 60-D spike N. side [old blaze]
- [2] 5" R. Pine S30°E 54.65 set 60-D spike E. side
- P. Pole N80°E 161.00 Set 60-D spike N. Side
- P. Pole S75°W 106.88 Set 60-D spike N. side

Signed by Bruce J. Jenema Date September 29, 1995
 Surveyor's Michigan License No. 25850