

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Manistee  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                    |   |            |   |            |                   |
|------------------------------------|---|------------|---|------------|-------------------|
| 1. Public Land Survey              | T | <u>24N</u> | R | <u>14W</u> | <u>G-7(SE 16)</u> |
|                                    | T | _____      | R | _____      | _____             |
|                                    | T | _____      | R | _____      | _____             |
|                                    | T | _____      | R | _____      | _____             |
| 2. Property Controlling in Section | S | _____      | T | _____      | _____             |
|                                    | S | _____      | T | _____      | _____             |
| 3. Miscellaneous Property in Sec.  | S | _____      | T | _____      | _____             |
|                                    | S | _____      | T | _____      | _____             |

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**

*95-450 at 9:45 AM*  
**NOV 17 1995**

*Ketorah Six*

**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Bruce J. Jenema in a field survey on September 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 15,16,21 and 22 Established by John Brink DS 8-11-183 Page 104 Set Post Birch 8" S08°W 10 links Beech 7" N42°E 20 links [now extinct Book "A", page 273 J.H. Mallard Dec. 1898 New BT's to old corner [1] 18" sugar S27°E 25.5 links [2] 8" Sugar N50°W 31 links; Book B, page 52 J.H. Mallard 1899 stake in road witness [1] and [2] [3] 7" Beech N42°W 20 links; Book B, page 198 J.H. Mallard Found stake and BT's "set iron in North-South Road" witness: [1], [2] and [3]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

LCRC No. 76-02 H. Brunning Found Iron  
 LCRC No. 83-04 C.F. Roser Found and accepted iron bar  
 1960 used by Ken Ostling DNR Survey not witnessed.  
 Manistee County Road Commission witnessed 4-1983  
 Manistee County Road Commission additional witnessed-undated  
 Found PK nail in center line confirmed by above witnesses.  
 However by our search we discovered 1 1/4" gas pipe of unknown length, 4 glass bottles and remains of wooden stake 1.5' below Road surface and 7.20 ft. West of above PK nail  
 Corner G-27 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Demarcation Act, MCL 54.281 et seq.). Date of Peer Review: NOV 07 1995



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On September 14, 1995 Accepted the 1 1/4" gas pipe as a careful and faithful re-establishment of the position of the original corner and installed a 2"x30" stainless steel pipe with a brass ID cap enclosed within a monument box and witnessed by:  
 P. pole S52°W 70.03 ft. Found Duplex Nail and washer West side  
 10" R. Pine N66°E 58.75 ft. Found 50-D Spike on South side  
 SE corner Twp. Hall N43°W 68.67 ft.  
 6" Maple N22°E 132.23 ft. Set 60-D spike West side  
 Found PK at the centerline intersection of N-S & E-W Roads Easterly 7.20 ft.

Signed by Bruce J. Jenema

Date September 22, 1995

Surveyor's Michigan License No. 25850