

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee

(County)

Located In:

Corner Code #/

1. Public Land Survey

T 24N R 14W
T _____ R _____
T _____ R _____
T _____ R _____

H-07 S¹/₄ Sec. 15

2. Property Controlling
in Section

S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REGISTER'S OFFICE
MANISTEE COUNTY

96-468 at 3:35 pm

OCT 16 1996

Reborah Six

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Bruce J. Jenema, in a field survey on September 5, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-07 S 1/4 corner of Section 15, T24N, R14W
John Brink 1839 DNR ESTABLISHED BY K. OSTLING 1960
16" Sugar for 1/4 Sec. post (4) 4" J. Pine N51°W 66 1/2 links (43.89')
Jan. 24, 1905 J.H. Millard (5) 13" Maple S19°E 31 1/2 links (20.79')
Found stump of corner, Sugar, The DNR surveyors place this corner on line
with marks lying near witnessed between Section corners at the appropriate
(1) 10" Beech S54°W 10 links prorated distances this falls 3 links East
(2) 12" Sugar S69°W 67 links of fence line South.
(3) 30" Hemlock S04°W 128 links LCRL # 83-04 CF ROBERT 5-2-1983

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On August 26, 1996, I found a DNR 1" iron pipe & cap in good condition.



Corner H-07 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1996, as amended, (being the State Survey and Monument Act, MCL 54.261 et. seq.). Date of Peer Review: SEP 17 1996

Anthony M. Slawinski

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On Aug. 26, 1996, I found the 1" iron pipe & ID cap placed by the DNR and in good condition

~~On Aug. 26, 1996, I installed a Manistee County Monument, within a monument box in the exact location of the above DNR 1" iron pipe and is accepted as a careful & faithful re-establishment of the position of the original corner and witnessed by:~~

- (6) 20" Maple S13°E 8.83' Face of blaze NBT
- (7) 12" R. Pine S70°W 49.42' 60-D S. side
- (4) 12" J. Pine N46°W 44.13' Blazed root 60-D S. side
- (8) 14" Tw. Sugar S60°E 82.61' 60-D spike S. side

This corner is 5' South of a sand trail road.

Signed by Bruce J. Jenema Date September 5, 1996

Surveyor's Michigan License No. 25850

