

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|-----------------------|
| 1. Public Land Survey | T | <u>24N</u> | R | <u>14W</u> | <u>I-02 [E 1/4 3]</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

**REGISTER'S OFFICE
 MANISTEE COUNTY**

#95-395 AT 1:45 p.m.
 OCT 09 1995

Penny A. Pepera
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3	●	2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Bruce J. Jenema, in a field survey on September 11, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

one-quarter corner common to Sections 2 & 3, Established by John Brink D.S. 8-11-1839 Page 102
 Set post and witnessed by: Sugar 14" N29°E 1 link, Hemlock 12" S71°W 13 links
 Book A page 266 May 1st, 1907 Stone 1907 EWM
 Book B page 150 "Previously established"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

LCRC H.R. Brunning #73-11 Found 1/2" iron Witnessed:
 [1] 6" Maple NE 65.82 [2] Cherry Stump SE 89.25
 Certified survey W.B. Batzer 1976 Liber 1 page 364 Set nail from witnesses
 [3] S30°W 113.79 P.pole [4] West 33.60' 18" Elm Stump
 [1] N49°E 65.25 ft. 8" Maple
 MCRC updated witnesses [5] P.pole S20°W 100.33 nail NW side
 [6] N56°E 8" Hard Maple 64.92 40-D spike NW side
 [7] N32°E 5" Hard Maple 84.45' Duplex with tag
 [4] Dodt witness 1960

16" ELM WEST 33.5
 Corner 1 - 2
 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: OCT 3 1995



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

September 11, 1995 Accepted 1/2" iron as a careful and faithful re-establishment of the position of the original corner and installed a 2"x30" stainless steel pipe with a brass ID cap enclosed within a monument box and witnessed by:
 [4] Elm stump West 33.20 Nail & washer S side poor condition
 [6] 8" Maple N56°E 64.98 Found 40-D spike West side
 [5] P.pole S21°W 100.03 Found #8 Duplex West side
 [7] 5" Maple N32°E 84.41 Found Duplex with tag
 12" Maple N45°E 80.00 Set 60-D West side
 P.pole N07°W 147.88 Set 60-D East side

Signed by Bruce J. Jenema Date September 29, 1995
 Surveyor's Michigan License No. 25850