

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manistee</u> <small>(County)</small>	Located In:	Corner Code \neq
Public Land Survey	T <u>24N</u> R <u>14W</u>	<u>I-3 (SE 3)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

REGISTER'S OFFICE
MANISTEE COUNTY
 95-451 at 9:50 AM
NOV 17 1995
Rebecca Six
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Bruce J. Jenema in a field survey on **September 13**, 19**95**

to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
 Corner common to Sections 2,3,10 and 11 Established by John Brink D.S. 8-11-1839 Set post and witnessed by: Beech 12" S52°E 14 links and Beech 8" S42°W 18 links
 Book A page 265 1899 J.H. Mallard Stake and BT's found;
 Book B page 28 J.H. Mallard stake and BT's
 1902 Harrison Knight previous est. from old BT's
 1909 EWM Found stake and BT's and gas pipe
 Cedar STP 16" S66 1/2°W 22 1/2 links Hemlock 24" N13 1/2°W 27 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 On September 13, 1995 Found 1/2"x22" iron and part of 1" pipe pinched off pipe at bottom of hole at the intersection of Vondra and Kurick Road
 Excavated the area, did not find a gas pipe
 Certified survey by W.B. Batzer Dec. 1975 Found 1/2" iron rod
 [1] N35°E 76.25' 6" R.Pine [2] N56°W 57.32' P.pole
 [3] West 43.24' 24" Poplar [4] S40°W 68.06' 10" Elm
 [5] N50 1/2°E 155.75' P.pole

Corner 1 - 3 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Monument Act, MCL 54.261 et seq.). Date of Peer Review: NOV 7 1995

Anthony M. Stancovich



Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 On 9-13-1995, Accepted 1/2" iron bar as a careful and faithful re-establishment of the position of the original corner and installed a 2"x30" stainless steel pipe with a brass ID cap enclosed within a monument box and witnessed by:
 N45°E P.pole 41.87' 60-D on the East side
 N50°W P.pole 53.32' 60-D spike on the East side
 N40°E 12" R.Pine 76.45' 60-D spike on the West side
 S52°E 8" Cedar 69.40' 60-D spike on the West side

Signed by Bruce J. Jenema Date September 29, 1995
 Surveyor's Michigan License No. 25850