

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee
(County)

Located In:

Corner Code #/

| | | | | | |
|------------------------------------|---|------------|---|------------|-----------|
| 1. Public Land Survey | T | <u>24N</u> | R | <u>14W</u> | I-4[E 10] |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

REGISTER'S OFFICE
MANISTEE COUNTY

95-452 at 9:55 AM
NOV 17 1995

Deborah Dix

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Bruce J. Jenema, in a field survey on September 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 5 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |


A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 10 and 11 Established by John Brink D.S. 8-11-1839 Set one-quarter corner post page 101 Government Book and witnessed by:
 Beech 6" N15°W 8 links Beech 8" S71°W 11 links
 JHM 1899 Established and set brick and iron. Witnessed by:
 Hemlock 24" N83°W 31 1/2 links Hemlock S12°E 12 links
 Book B page 28 JHM 1899 Same as above

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found PK nail midway and on line between the NE corner of Section 10 and the Southeast corner of Section 10 Set by B.J.Jenema Sept.20,1993
 Witnessed by: [1] P.pole S62°E 30.17' [2] P.pole S70°E 25.00
 [3] 8" R. pine N35°W 60.35'
 Trail road running to the East, this area the road has been cut 3-4 ft.

Corner I-4 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Monument Act, MCL 54.261 (1) (a) (i)). Date of Peer Review: NOV 7 1995 *Anthony M. Hauke*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On September 11, 1995, Accepted PK nail as a careful and faithful re-establisher of the position of the original corner and installed a 2"x30" stainless steel pipe with a brass ID cap enclosed within a monument box and witnessed by:
 [1] P.Pole S62°E 30.17' Found 60-D spike South side
 [2] P.Pole S70°E 25.00' Found 60-D spike North side
 12" R.Pine N35°W 62.68 Set 60-D spike West side
 14" R.Pine N30°W 69.14 Set 60-D spike West side
 Utility guard post N58°E 47.18 ft. Set 60-D South side

Signed by Bruce J. Jenema Date September 29, 1995
 Surveyor's Michigan License No. 25850