

OCT 28 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee (County) Located In: Corner Code #
1. Public Land Survey T 24N R 14W M-07 SE Sec Corner Sec 13
2. Property Controlling in Section S T R SW Sec Cor Sec 18
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

REGISTER'S OFFICE
MANISTEE COUNTY
00-306 At 11:49 a.m.
SEP 03 2000
Penny A. Repora
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Anthony M. Slawinski, in a field survey on June 2, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Southeast Section Corner Section 13 (24-14) & Southwest Section Corner Section 18 (24-13) Set by John Brink in 1837.
1. Maple 6" in dia. S 24° W 19 links (12.54')
2. White Pine 13" in dia. N 52 1/2° W 25 links (16.50')

Manistee County Surveyor's Record
By Millard in 1908, found stake set by Brink
3. Elm 20" in dia. S 20 1/2° E 56 links (36.90')
4. Elm 12" in dia. N 81° E 85 links (56.10')

Land Corner Record by Kenneth Ostling RLS #10068, in 1960. (Rec. 70-32)
Set 1"x24" pipe on line & equidistant, over 1/4 and section corner To the North. This checked exactly to stream east & is slightly Short of record to 1/4 corner East.
5. Corner Fence Post N 43° E 45 links (29.70')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Southeast Section Corner Section 13 (24-14) & Southwest Section Corner Section 18 (24-13) On June 2, 2000, I, Anthony M. Slawinski along with a field crew from Abonmarche found a 1"x 24" iron pipe set by Ostling. We found no other evidence to dispute this location for the corner.

Condition of witnesses: #1 gone, #2 gone, #3 gone, #4 gone & #5 gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Southeast Section Corner Section 13 (24-14) & Southwest Section Corner Section 18 (24-13) On June 2, 2000, I placed a Manistee County Monument, in the exact location as the above mentioned 1"x 24" iron pipe as a careful and faithful re-establishment of the position of the original corner, and witnessed by:

- 6. N 30° W 25.74' 15" Poplar (set 60d on NE side of tree)
7. S 55° W 27.53' 6" Poplar (set 60d on W side of tree)
8. S 17° E 28.29' 6" Poplar (set 60d on E side of tree)
9. N 40° E 47.62' (set 1/2" iron rod)

Thompsonville Road makes a 90° turn at this corner. The corner is in the centerline, centerline intersection of Reed Road and of Thompsonville Road, ±6" below grade.



Corner M - 0 7 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: 7-31-00
Anthony M. Slawinski

Signed by Anthony M. Slawinski
Surveyor's Michigan License No. 13597

Date 7-26-00

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.