

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 15 W.	K-6; K-7
2. PROPERTY CONTROLLING IN SECTION	14, T. 24 N. R. 15 W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 22, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-6 Reestablished corner on line between section corners to N and S, which falls in old vague road R.O.W.; and at double the distance of Sec. corner & 1/16 corner to N. This position seems to best fit J.H. Millard split-up of Sec. 13 in 1907.
- K-7 Restored corner from J.H. Millard witness dated 1900 and 1907. Corner is 10'± SE of approximate intersection of old township road grades E-W-N. Corner fits his survey of Section 13.
- 15 Established 1/16 corner equidistant and on line between section corner to W and 1/4 corner to E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6	K-7	15
Set DNR mon. & cedar post	Set 1 1/4"x36" Pipe	Set 1 1/4"x36" Pipe & cedar post w/loc. tag
8" Trpl. Cherry N85°E 41.3	5" Maple N30°E 59.5	9" Cherry N20°W 26.61
6" Trpl. Maple S53°E 66.2	13" Cherry S55°E 50.8	9" Maple S18°E 17.07
8" W. Pine S64°W 11.5	13" Maple S57°W 30.8	7" Maple S37°W 21.11
Center N-S Winding Trail	Set cedar post w/loc. tag	Center E-W Sand Trail
Due E 6±	N45°W 33	Due N 8


SIGNED BY Carl F. Roser 9-4-75 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



PLEASANTON TOWNSHIP
MANISTEE COUNTY