

Manistee Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>24</u> ^{N.} XX , R. <u>15</u> ^{E.} XX W.	A-11 A-13
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION <u>31</u>	, T. <u>24</u> ^{N.} XX , R. <u>15</u> ^{E.} XX W.	M.C. 1632.5' S of B-11
4. LOT NO. _____	, RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 7-17 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 7-20- 1972, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-11 Reestablished lost corner by single proportion per Std. B.L.M. directions.
- A-13 Recovered 1" Square Iron. Corner of long standing and acceptance by local RLS's.
- M.C. Recovered 6" round (homemade) concrete mon. Corner previously accepted and monumented by deceased RLS, Charlie Dodt. Point on N-S $\frac{1}{4}$ line on North Shore of Bear Lake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11			A-13			M.C.		
Set	Std. DNR Mon & gd.post		Fd. 1" Sq. Iron Bar			Fd. 6" Rd. Concrete Mon.		
18" W. Pine	S27E	12.7'	9" Maple	N45E	66.32'	10" W. Pine	N58W	20.48'
7" Tamarack	S23W	14.8'	30" Maple	N41W	52.20'	24" W. Pine	N12W	30.40'
8" Tamarack	N20W	16.6'	20" tw Oak	S58W	38.82'	20" Maple	N 5E	20.22'


SIGNED BY Carl F. Roser DATE 12-4-72

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____