

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MANISTEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T. 24N R. 15W

C-6

2. Property Controlling In Section

S. T. R. S. T. R.

3. Miscellaneous S. Property in Sec.

T. R. S. T. R.

4. Lot No. Recorded Plat

5. Private Claims

REGISTER'S OFFICE MANISTEE COUNTY

#96-364 AT 10:15 A.M.

AUG 23 1996

Penny A. Popera REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Kenneth L. Ross, in a field survey on July 24, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6 1/4 Cor., 17 & 18-24-15

1839 John Brink

- (1) 8" Beech S 35 W 13 lks
(2) 8" Beech N 65 W 11 lks

Grid with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6 1/4 Cor., 17 & 18-24-15

Aug., 1971, Slawinski Pd. 1" x 1" Iron St. (Liber 1, Page 9)

- (3) 30" Beech (tag) SE 24.25'
(4) 12" Maple (tag) NW 17.26'
(5) 8" Beech (tag) North 9.87'

Jul., 1996, K. Ross Pd. 1" x 1" x 16" Square Iron, Fence N & W

Corner C-6 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: AUG 6 1996

Anthony Slawinski

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 1/4 Cor., 17 & 18-24-15

Pd. Witness #4 (now 19") & 5 (top broken off)

Witness #1, 2, & 3 gone.

Replaced 1" x 1" x 16" Square Iron with Standard Manistee County Monument, and is attached to the best available evidences of the original corner.

- (6) 13" Maple S 35 W 27.03' (Spike)
(7) 19" Beech S 31 E 34.50' (Spike)
(8) 12" Beech S 68 E 8.60' (Spike)

Signed by [Signature] 8-5-96 Date

Surveyor's Michigan License No. 17634

