

SURVEY  
REMONUMENTATION

MAY 1 5 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MANISTEE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 24N R 15W D-5 \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER'S OFFICE  
MANISTEE COUNTY  
96-410 at 3:00 PM  
SEP 20 1996  
Reborah Six  
REGISTER OF DEEDS

I, Kenneth L. Ross, in a field survey on August 19, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-5 1/4 Cor., 8 & 17-24-15  
1839 John Brink  
(1) 6" Beech S 24 W 10 lks  
(2) 8" Beech N 34 W 22 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-5 1/4 Cor., 8 & 17-24-15  
Aug., 1996, K. Ross Fd. 1/2" Iron, 8' +/- North of CL Road, 2621.39' East of NW Section corner, 2620.93' West of NE Section corner

Corner D-05 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: SEP 17 1996

Anthony M. Slawski

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-5 1/4 Cor., 8 & 17-24-15  
Witness #1 & 2 gone.  
Replaced 1/2" Iron with Standard Manistee County Monument in monument box, and is accepted as the best available evidence of the original corner.  
(3) Power Pole N 25 W 23.40'  
(4) 10" W. Pine N 57 W 81.51'  
(5) Cor. Fence Post S 02 W 51.50'  
(6) Fiber Opt. Cable Marker S 22 E 66.66'

Signed by [Signature] Date 9-17-96

Surveyor's Michigan License No. ~~17634~~ 17634

