

1993

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in  
Manistee  
(County)

Located In: Corner Code #

- |                                    |   |     |   |     |     |
|------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey              | T | 24N | R | 16W | H-1 |
|                                    | T |     | R |     |     |
|                                    | T |     | R |     |     |
|                                    | T |     | R |     |     |
| 2. Property Controlling in Section | S |     | T | R   |     |
|                                    | S |     | T | R   |     |
| 3. Miscellaneous Property in Sec.  | S |     | T | R   |     |
|                                    | S |     | T | R   |     |

REGISTER'S OFFICE  
MANISTEE COUNTY  
#93-585 AT 11:58 A.M.  
OCT 6 1993

*Penny A. Papp*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard Hays, in a field survey on September, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**H-1 NORTH QUARTER CORNER OF SECTION 3**  
Not set in Original Survey.  
1961 corner was set by William R. Downey, Registered Land Survey for M.S.H.D. Set 3/4" Pipe from Road Plan Information.  
Project 51-13. (1937 Survey) File S17-AZ  
10" Ash S-21°-E 27.54'  
13" Norway Pine S-73°-E 38.25'  
15" Maple N-67°-E 41.00'  
Steel Fence Post  
L.C.R.C. Manistee Records  
88-634

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**H-1 NORTH QUARTER CORNER OF SECTION 03**  
Found 3/4" iron pipe set by William R. Downey and Witnesses.  
Replaced Iron pipe with a Standard Manistee County Monument with Brass Cap.

Corner H-01 ratified by the Manistee County Peer Group pursuant to P.A. 123 of 1915, as amended by P.A. 345 of 1990, as amended. Date of Peer Review: **APPROVED OCT 4 1993**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**H-1 NORTH QUARTER CORNER OF SECTION 03**  
Set Standard Manistee County Monument with Brass Cap and accepted as the best available evidence of the position of the Corner, the following Witnesses:  
13" Red Pine S-74°-E 38.18'  
14" Maple S-64°-W 41.04'  
14" Ash S-20°-E 27.29'  
12" Beech S-38°-W 24.64'  
1/2" Iron Pipe West 16.92'  
Steel Fence Post South 1.0'

Signed by Richard Hays Date Sept 30 1993  
Surveyor's Michigan License No. 25847

