

1993

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in  
Manistee

(County)	Located In:	Corner Code #
1. Public Land Survey	T 24N R 16W	I-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER'S OFFICE  
MANISTEE COUNTY

#93-638 AT 10:00 A.M.

NOV 3 1993

*Penny A. Pepera*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Richard L. Hays, in a field survey on October 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4 1/4 CORNER COMMON TO SECTIONS 10 & 11  
1838 Not set in Original G.L.O. Survey.

1978 Survey by Northwest Survey & Engineering Co.

Found Plow Point with witnesses:

- 12" Ash N-80°-W 45.41'
- 4" Tw. Cedar N-60°-E 24.20'
- 12" Cedar S-18°-W 46.76'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4 1/4 CORNER COMMON TO SECTIONS 10 & 11  
Found Plow Point and Witnesses from Northwest Survey & Engineering Co. Survey. Also found Old Fence Line to the South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


I-4 1/4 CORNER COMMON TO SECTIONS 10 & 11  
Replaced Plow Point with standard Manistee County Monument with Brass Cap stamped to identify corner. This position was not established by the Original Government Surveyors. This Monument is accepted as the best available evidence of the position of the Corner.

- 15" Cedar S-22°-W 46.60'
- 11" Ash S-45°-E 44.58'
- 7" Cedar N-58°-E 24.19'
- 16" Ash N-74°-W 45.43'

Old Fence Line to the South and 2' South of Center line of old grade.

Signed by Richard L. Hays Date Oct 28, 1993

Surveyor's Michigan License No. 25847



Corner I-4 ratified by the Manistee County Peer Group pursuant to P.A. 123 of 1975, as amended by P.A. 345 of 1990, as amended. Date of Peer Review: NOV 2 1993