

JUL 18 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manistee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>16W</u>	<u>K-13</u>
	T _____ R _____	<u>SE Sec Corner</u>
	T _____ R _____	<u>Sec 35</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER'S OFFICE  
 MANISTEE COUNTY  
 CO-281 At 10:30 p.m.  
 SEP 03 2000  
*Penny A. Repora*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Anthony M. Slawinski, in a field survey on June 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Southeast Section Corner Section 35 (24-16)  
Set by John Brink in 1838  
1. Sugar 14" in dia. N 84° E 7 links (4.62')  
2. Sugar 14" in dia. N 46° W 47 links (31.02')  
Northeast Corner of Section 2 (23-14) was set by Brink, West 65 links (42.90')

Certificate of Survey, by Anthony M. Slawinski in 1989.

Found spike  
3. Maple 30" in dia. S 30° E 36.57'  
4. Pine 10" in dia. S 55° W 90.52'  
5. Oak 28" in dia. N 35° E 69.16'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Southeast Section Corner Section 35 (24-16)  
On June 16, 2000, I Anthony M. Slawinski along with a field crew from Abonmarche found a 60d spike raised over another 60d spike 0.50' South of the centerline of 13 mile road. We found no other evidence to dispute this location for the corner.

Condition of witnesses: #1 gone, #2 gone, #3 good, #4 gone, #5 gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Southeast Section Corner Section 35 (24-16)  
On June 16, 2000 I placed a Manistee County Monument, in a monument box, in the exact location of the above mentioned 60d spike as a careful and faithful re-establishment of the position of the original corner, and witnessed by:

- 3. S 25° E 36.47' 30" Maple (fd. nail w/ washer on E. side of tree)
- 6. West 27.66' 1/2" iron rod
- 7. N 38° E 68.64' 30" Maple (fd. 40d spike on W. side of tree)
- 8. S 62° W 88.63' Center of a Telephone Man Hole cover

Corner is 0.50' South of the centerline of 13 Mile Rd.  
Corner is in the centerline of Erdman Road as it runs North from 13 Mile Road.



Corner K-13 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: 7-31-00

*Anthony M. Slawinski*

Signed by Anthony M. Slawinski

Date 7-27-00

Surveyor's Michigan License No. 13597