

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Manistee
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 24N R 16W L-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

REGISTER'S OFFICE
 MANISTEE COUNTY
 # 93-635 at 9:50 A.M.
 NOV 3 1993
Penny A. Rogers
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Bruce J. Jenema, in a field survey on October 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1 General Land Office did not set this corner
 Established by Holden 1915 & Witness by: Elm 5" NO9°E 65 links
 Holden recorded distance from the Northeast corner of Section 1 2626.80 ft.
 (Measured 2626.53)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" square iron Bar at the intersection of Old fence lines N,S,E,W, the same iron found & accepted by Gourdie-Fraser and Associates 12-2-88 & Witnessed by:
 6" Ash North 7.1'
 10" B.Cherry N80°E 23.0'
 10" Maple S10°E 21.0'
 ALSO: Found cobble stones around remains of wooden stake

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

North 1/4 corner Section 1, T24N, R16W
 A 2"x30" Stainless Steel pipe replaces remains of wooden stake
 N65°W 8" Ash 12.50' Set 60-D spike
 S10°E 10" Maple 20.54' Set 60-D spike
 N80°E 10" B.Cherry 24.25' Found #16 Nail
 N90°E 6" Ash 7.30' Set 60-D spike
 N40°W 1" iron 0.36'

Corner L-1 ratified by the Manistee County Peer Group pursuant to P.A. 123 of 1915, as amended by P.A. 345 of 1990, as amended. Date of Peer Review NOV 11 1993



Signed by Bruce J. Jenema

Date October 28, 1993

Surveyor's Michigan License No. 25850