

July 1, 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee (County) Located In: Corner Code #
1. Public Land Survey T 24N R 16W L-13
S 1/4 Sec 36
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

REGISTER'S OFFICE
MANISTEE COUNTY
00-287 at 10:33p.m.
SEP 03 2000
Penny A. Pepera
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Anthony M. Slawinski, in a field survey on June 16, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

South 1/4 Corner Section 36 (24-16)
Set by John Brink in 1838
1. Beech 8" in dia. N 29 1/2° E 35 links (23.10')
2. Beech 6" in dia. N 37 1/2° W 31 links (20.46')

Certificate of Survey, by Anthony M. Slawinski in 1987.
Fd. PK Nail.
3. Jack Pine 10" in dia. N 30° W 68.61'
4. Jack Pine 12" in dia. N 15° W 77.71'
5. Jack Pine 10" in dia. N 5° E 56.56'

Certificate of Survey, by Bruce J. Jenema RLS #28450, in 1991.
Fd. #60d Nail
5. Red Pine 8" in dia. N 8° E 56.50'
6. Phone Box S 75° W 104.00'
7. White Pine 12" in dia. S 50° E 81.40'

Certificate of Survey, by Daniel B. Zwar RLS #28435, in 1999.
Fd. PK nail.
3. Pine 10" in dia. N 30° W 68.61'
4. Pine 12" in dia. N 15° W 77.71'
5. Pine 10" in dia. N 5° E 56.56'
C/L E-W Road

B South 1/4 Corner Section 36 (24-16). Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On June 16, 2000, I Anthony M. Slawinski along with a field crew from Abonmarche found a PK nail in the centerline of 13 Mile Rd. We found no other evidence to dispute this location for the corner

Condition of witnesses: #1 gone, #2 gone, #3 good, #4 good, #5 gone, #6 gone & #7 gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 1/4 Corner Section 36 (24-16)

On June 16, 2000, I installed a Manistee County Monument, in a monument box in the exact location of the above mentioned PK nail as a careful and faithful re-establishment of the position of the original corner, and witnessed by:

- 3. N 30° W 67.55' 12" Jack Pine (fd. 60d spike in E. side of tree)
4. N 12° E 77.33' 14" Jack Pine (fd. nail & washer in E. side of tree)
8. S 29° E 60.51' 10" Pine (fd. 60d spike in E. side of tree)
9. N 05° W 60.51' 10" Pine (set 60d spike in E. side of tree)

Corner is in the centerline of 13 Mile Road.

Corner L-13 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: 7-31-00
Anthony M. Slawinski

Signed by Anthony M. Slawinski
Surveyor's Michigan License No. 13597



Date 7-26-00

Grid table with columns A-L and rows 1-13. Cell 13,36 contains a black dot.