

SEP 30 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... 17N N. 15W E. A1
2. PROPERTY CONTROLLING IN SECTION... T. S., R. W.
3. MISCELLANEOUS PROPERTY IN SECTION... T. N. S., R. W.
4. LOT NO. RECORDED PLAT
5. PRIVATE CLAIMS

FILED AT 2 O'CLOCK P M SEP 23 1993 MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 30 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to section 6 of T17N R15W, section 1 of T17N R16W, section 31 of T18N R15W and section 36 of T18N R16W

1835 survey by Mullett & Brookfield Set Wood Post Y.Pine 16" S68W 42 links W.Oak 14" N34E 24 links
1943 survey by R.S. Copeland Found a rusted iron pipe Wood Post North 1 link
1970 survey by Robert A. Griffin Fd. 1" I.P. & replaced w/ 5x60 conc. monu. R.Pine 3 N7E 86.47' R.Oak 7 S11E 65.92' W.Oak 8 N79W 27.68' P.Post 4"x7' North 1.7'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 60" long concrete monument w/brass cap and all the witnesses to be in good condition. The monument extends 1.5' above the surface. Liber 1 Page 185 documents the history of this corner as perpetuated by Robert A. Griffin. Griffin believed the bearing on the Y.pine was reversed and should have been N68E. He found a R.Pine stp. at N68E 42 links from the iron pipe. I could not find evidence of this stump. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section corner common to section 6 of T17N R15W, section 1 of T17N R16W, section 31 of T18N R15W and section 36 of T18N R16W

Monu. 5" sq. by 60" long concrete monu. with 3" brass disk left in place. Witnesses W.Pine 2 East 37.62' B.Oak 11 S11E 65.92' W.Oak 11 N79W 27.71' R.Pine 7 N5E 86.48' P.Post 4 North 1.7' CL of E-W 2-track North 50'

Peer Group Reviewed and Approved Date: 9-16-93 Kenneth L. Ross Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE



LIBER 3 PAGE 104

SURVEYOR'S MICHIGAN REGISTRATION NO.