

SURVEY & REMONUMENTATION

SEP 30 1993

Commissioner

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	17N N. 15W E. S., R. W.	A3
2. PROPERTY CONTROLLING IN SECTION _____, T. _____	N. S., R. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____	N. S., R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

FILED

AT 2 O'CLOCK P M

SEP 23 1993

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 23 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to sec's. 6 & 7 of T17N R15W and sec's. 1 & 12 of T17N R16W

1835 survey by Mullett & Brookfield Set Wood Post Y.Pine 16 S72W 44 links Y.Pine 15 N62W 64 links	1935 field notes of Cook (USFS) Indicates the corner is marked by an Oak Stake near the P.M. River.	1972 survey by Robert A. Griffin Fd. the remains of the rotted wood wood stake & replaced w/ a 5" sq. x 60" lng conc. monu. w/brass cap. W.Oak 4 N79E 51.42 feet W.Oak 7 S4E 56.20 feet W.Oak 8 S53W 69.38 feet B.Oak 4 N27W 6.15 feet P.Post 4"x7" South 1.7 feet
1943 survey by R.S. Copeland Corner is a rotted wood stake P.Post North 2 links	1993 survey by Richard Hays Fd. conc. monu. by Griffin N1/4 7 S89-32-45E 2606.06 feet W1/4 7 S02-39-11E 2648.68 feet Recorded Liber 430 Page 1090	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 60" long concrete monument w/ brass cap by Griffin rising 18" above the surface and 310 feet east of the centerline of Indian Trail and 83 feet south of the centerline of an E-W 2-track. Liber 1 Page 186 by Griffin documents the history of this corner. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 corner common to section 1 of T17N R15W and section 6 of T17N R14W

Monu. 5" sq. by 60" long concrete monu. with 3" brass disk was left in place.

Witnesses:

W.Oak 7 N79E 51.47'
W.Oak 10 S6E 56.17'
W.Oak 12 S51W 69.40'
B.Oak 7 N27W 6.15'
P.Post 4"x7' South 1.7'

Peer Group Reviewed and Approved
Date: 9-16-93
Kenneth L. Ross
Mason County Surveyor


SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 107

SURVEYOR'S MICHIGAN REGISTRATION NO. _____