

MAR 08 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mason

(County)

Located In:

Corner Code //

- 1. Public Land Survey T17N R 15W
T17N R 15W
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

B-5
A-4 ✓

- 4. Lot No. , Recorded Plat
- 5. Private Claims

I, **Richard Hays**, in a field survey on **August**, 19**92**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

B-5 S 1/4 CORNER OF SECTION 07
1838 G.L.O.
18" Aspen S-76°-E 28 Links
48" Pine N-45°-E 30 Links

A-4 W 1/4 CORNER OF SECTION 07
1838 G.L.O.
White Pine N-17°-W 41 Links
White Pine S-19°-W 14 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5 S 1/4 CORNER OF SECTION 07
Corner falls in clear cut area. Set at prorated distance and on line between the Southwest Corner and the southeast Corner of Section 07.

A-4 W 1/4 CORNER OF SECTION 07
Found White Pine Stump which fits the G.L.O. N-17°-W 27.00'. Could not find the White Pine Stump to the Southwest. Held Found Iron for Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 S 1/4 CORNER OF SECTION 07
This monument is accepted as the best available evidence of the position of the Corner. Set 2 1/2 Iron Pipe Monument stamped to identify Corner:
8" R. Oak N-44°-E 57.78'
9" R. Oak N-26°-W 114.81'
7" W. Oak S-71°-W 189.18'
11" R. Pine S-44°-E 168.95'
Carsonite Post North 0.50'

A-4 W 1/4 CORNER OF SECTION 07
This monument is accepted as the best available evidence of the position of the Corner. Set 2 1/2 Iron Pipe Monument stamped to identify Corner:
10" W. Oak N-66°-E 30.24'
6" W. Oak N-73°-W 47.55'
10" R. Oak S-31°-W 25.81'
11" W. Oak S-51°-E 32.82'
Carsonite Post West 0.50'

FILED
AT 11 O'CLOCK 9 M
1993
MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by *Richard Hays*
Surveyor's Michigan License No. 25847

Date 6/25/93

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28 1971
REVISED MAY 14 1975
REVISED JAN 1981
Mason County Surveyor

