

**SURVEY &  
REMONUMENTATION**

MAR 08 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mason  
(County)

Located In: Corner Code //

FILED  
AT 11 O'CLOCK 9  
MARY GOLDEN KOLASKI  
MASON COUNTY  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

- 1 Public Land Survey  
T 17N R 15W B-3  
T 17N R 15W C-4  
T R  
T R
- 2 Property Controlling S T R  
in Section S T R
- 3 Miscellaneous S T R  
Property in Sec. S T R
- 4 Lot No. Recorded Plat
- 5 Private Claims

Richard Hays in a field survey on August 19 92  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	P
2	6	5	4	3	2	1						
3	7	8	9	10	11	12						
4	18	17	16	15	14	13						
5												
6	19	20	21	22	23	24						
7												
8	30	29	28	27	26	25						
9												
10	31	32	33	34	35	36						
11												
12												
13												

A. Description of original monument and accessories and/or subsequent restoration.

**B-3 N $\frac{1}{4}$  CORNER OF SECTION 07**  
1838 G.L.O.  
12" Beech N-37°-E 30 Links  
14" Beech S-45°-E 20 Links

**C-4 E $\frac{1}{4}$  CORNER OF SECTION 07**  
1838 G.L.O.  
12" Beech N-19°-W 34 Links  
6" Ash S-49°-E 49 Links  
1960 Concrete Monument set by  
George Blass. 1972 U.S.F.S. Monument  
set by R. Griffin - Recorded Liber 1,  
Page 191.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**B-3 N $\frac{1}{4}$  CORNER OF SECTION 07**  
Found the remains of a U.S.F.S.  
Post and a rotted wood stake,  
1.4' North of U.S.F.S. Post.  
Post could have been set by  
R.S. Copeland in 1943 as per  
the Northwest Corner - Recorded  
Liber 1, Page 186

**C-4 E $\frac{1}{4}$  CORNER OF SECTION 07**  
Found U.S.F.S. Monument set by  
R. Griffin - Recorded Liber 1, Page 191

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**B-3 N $\frac{1}{4}$  CORNER OF SECTION 07**  
This monument is accepted as  
the best available evidence of  
the position of the Corner.  
Set 2 $\frac{1}{2}$ " Iron Pipe Monument stamped  
to identify Corner:  
5" W. Oak N-60°-E 14.68'  
10" R. Pine N-66°-W 23.21'  
9" R. Pine S-49°-W 42.96'  
10" R. Pine S-84°-E 41.82'  
Carsonite Post East 1.75'  
Signed by *Richard Hays*

**C-4 E $\frac{1}{4}$  CORNER OF SECTION 07**  
Found a 5"x5' Square Concrete Monument  
stamped to identify Corner:  
4" R. Pine N-45°-E 52.99'  
6" R. Pine S-88°-E 48.95'  
6" R. Pine S-43°-W 37.63'

Surveyor's Michigan License No

*Richard Hays*  
25847

LIBER 3 PAGE 151  
Date 5/11/93  
Free Group Enclosed and signed

RICHARD  
L HAYS  
LAND  
SURVEYOR  
NO.  
25847