

**SURVEY & REMONUMENTATION**

SEP 30 1993

**LAND CORNER RECORDATION CERTIFICATE**

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>17N</u> N. <u>15W</u> E. S., R. _____ W.	C3
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**FILED**

AT 2 O'CLOCK P

SEP 23 1993

**MARY GOLDEN KOLASKI**  
MASON COUNTY REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 23 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Section corner common to sections 5, 6, 7 and 8 of T17N R15W**

1838 survey by John Hodgson Set Wood Post Pine 24 S51E 25 links Pine 18 N15W 42 links	1960 survey by George Blass 1/2" x 18" Pipe B.Oak 18 N46E 36.50 feet W.Oak 10 S40E 55.15 feet B.Oak 10 S65W 47.30 feet B.Oak 18 N9W 28.50 feet	1972 survey by Robert A. Griffin Fd. the pipe by Blass and replaced w/ a 5" sq. x 60" long conc. monu. w/ brass cap. R.Pine 4 N79E 30.95 feet R.Pine 5 N47W 25.84 feet P.Post 4"x7" North 1.5 feet
--	---	--

1936 field notes of A.R.Yale (USFS)  
Could not find the corner.

1993 survey by Richard Hays  
Fd. Conc. Monu. by Griffin

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

I found the 5" square by 60" long concrete monument w/ brass cap by Griffin rising 12" above the surface and 19 feet north of the centerline of an E-W trail road. Liber 1 Page 190 by Griffin documents the history of this corner. Blass's B.Oak N46E is now 20", his W.Oak is now 14", his B.Oak S65W is really 14" S53W and his B.Oak N9W is now 20". This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Section corner common to sections 5, 6, 7 and 8 of T17N R15W**  
Monu. 5" sq. by 60" long concrete monu. with 3" brass disk was left in place.  
Witnesses:  
W.Pine 4 N8E 57.06'  
R.Pine 6 N77E 30.93'  
W.Pine 8 S6E 68.84'  
R.Pine 7 N49W 25.86'  
Fiberglass Post South 0.7'  
N1/4 7 N88-47-20W 2621.40' (Hays Liber 430 Page 1090)  
E1/4 7 S00-32-49W 2639.30' (Hays Liber 430 Page 1090)

Peer Group Reviewed and Approved  
Date: 9-16-93  
Kenneth L. Ross  
Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



LIBER **3** PAGE **108**

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_