

**SURVEY & REMONUMENTATION**

SEP 30 1993

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

FOR CORNERS OF--: LOCATED IN--:  
 1. PUBLIC LAND SURVEY T. 17N N. 15W E. S., R. W.  
 2. PROPERTY CONTROLLING IN SECTION T. N. S., R. E. W.  
 3. MISCELLANEOUS PROPERTY IN SECTION T. N. S., R. E. W.  
 4. LOT NO. , RECORDED PLAT  
 5. PRIVATE CLAIMS

CORNER CODE	NUMBER	FILED
C4	AT 2	O'CLOCK P
		23 1993
MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 23 19 93, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1/4 corner common to sections 7 and 8 of T17N R15W**
- 1838 survey by John Hodgson Set Wood Post Beech 12 N19W 34 links B.Ash 6 N49E 49 links
  - Undated survey by K.B. Stephens Monument 4" round by 36" long concrete monument.
  - 1972 survey by Robert A. Griffin Fd. the 4"x60" conc. monu. replaced w/ a 5" sq.x 60" long conc. monu. w/brass cap. P.Post 4"x7' North 1.2 feet R.Pine 3 N42E 52.99 feet R.Pine 6 S88E 48.95 72.62' R.Pine 6 S43W 37.63 feet
  - 1960 survey by George Blass Fd. Stephens monument NE cor. 7 North 2640.00 feet
  - 1993 survey by Richard Hays Fd. conc. monu. by Griffin NE 7 N00-32-49E 2639.30 feet SE 7 S00-40-24E ? feet Recorded Liber 430 Page 1090

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 60" long concrete monument w/ brass cap by Griffin rising 18" above the surface 475 feet North of the centerline of a NE-SW road. The monument has been shot and the concrete is deteriorating but remains solidly in place. Liber 1 Page 191 by Griffin documents the history of this corner. Richard Hays completed a survey of section 7 for the U.S. Forest Service in 1993 and completed a corner recordation form but I was unable to locate it in the Register of Deeds. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/4 corner common to sections 7 and 8 of T17N R15W**  
 Monu. 5" sq. by 60" long concrete monu. with 3" brass disk was left in place.  
 Witnesses:  
 R.Pine 7 N36E 53.02'  
 P.Post 4"x7' North 0.9'  
 Fiberglass Post West 1.5'  
 R.Pine 9 S89E 49.00'  
 R.Pine 6 N50W 38.61'  
 R.Pine 10 S39W 37.57'

Peer Group Reviewed and Approved  
 Date: 5-16-93  
 Kenneth L. Nees  
 Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 106

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_