

SEP 30 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY T. 17N N. 15W E. S., R. W.
2. PROPERTY CONTROLLING IN SECTION T. N. E. S., R. W.
3. MISCELLANEOUS PROPERTY IN SECTION T. N. E. S., R. W.
4. LOT NO., RECORDED PLAT
5. PRIVATE CLAIMS

FILED AT 2 O'CLOCK M SEP 23 1993 MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 23 19 93 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to sections 17, 18, 19 and 20 of T17N R15W

1838 survey by John Hodgson Set Wood Post W.Oak 18 S60W 10 links W.Oak 12 N65E 47 links

1960 survey by G.Blass Monument is 3/8" iron pipe Sta. 199+68.08 west 17.97 feet

1972 survey by Robert A. Griffin Fd. 3/8" I.P. from Dysterhouse wits replaced w/ a 5" sq.x 60" long conc. monu. w/brass cap. R.Oak 16 S48W 69.69 feet R.Oak 12 N84W 92.33 feet W.Oak 16 North 17.65 feet P.Post 4"x7' North 1.2 feet

1909 survey by C.Landon Set wood Post W.Pine 16 S76E 116 links W.Pine 32 S61W 130 links

1940 survey by G.Dyksterhuse Fd. wood stake by Landon W.Oak 6 North 26.5 links Tw.W.Oak 7 N60W 67.5 links Tw.R.Oak 10 S35W 119.5 links USFS Post East 1 link

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: I found the 5" square by 60" long concrete monument w/ brass cap by Griffin rising 12" above the surface, 16.8 feet east of the centerline of the N-S road, 12 south of a fence line to the west, 23 north of a fence line to the east. Liber 1 Page 193 by Griffin documents the history of this corner. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section corner common to sections 17, 18, 19 and 20 of T17N R15W

Monu. 5" sq. by 60" long concrete monu. with 3" brass disk was left in place.

Witnesses:

R.Oak 20 S46W 69.69' P.Post 4"x7' North 1.2' W.Oak 18 N67W 49.02' W.Oak 20 N7W 17.51' W.Oak 8 S71E 16.44'

Peer Group Reviewed and Approved Date: 9-16-93 Kenneth L. Ross Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE



LIBER 3 PAGE 118

SURVEYOR'S MICHIGAN REGISTRATION NO.