

**SURVEY &
REMONUMENTATION**

SEP 30 1993

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

FOR CORNERS OF--: LOCATED IN--:
 1. PUBLIC LAND SURVEY T. 17N N. 15W E. S., R. W.
 2. PROPERTY CONTROLL- N. E. ING IN SECTION T. S., R. W.
 3. MISCELLANEOUS N. E. PROPERTY IN SECTION T. S., R. W.
 4. LOT NO. , RECORDED PLAT
 5. PRIVATE CLAIMS

CORNER CODE NUMBER D13	FILED AT 2 O'CLOCK P M SEPT. 23 1993 MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS
---------------------------	--

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 23 1993 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Standard 1/4 corner on the south line of section 32 of T17N R15W

1835 survey by Mullett & Brookfield
 Set Wood Post
 Beech 6 S64W 19 links
 Maple 7 N30E 14 links

1940 field notes of H. Arnouts (USFS)
 Monument is a wooden stake
 B. Oak 16 N32W 99 links
 W. Oak 14 N12E 57 links
 B. Oak 20 S70E 68 links

1972 survey by Robert A. Griffin
 Fd. a 1"x24" I.P. from Arnouts wits replaced w/ a 5" sq.x 60" long conc. monu. w/brass cap.
 W. Oak 14 S14W 47.49 feet
 P. Post 4"x7" North 1.2 feet
 W. Oak 14 S32E 87.75 feet
 W. Oak 28 N42E 123.47 feet
 N1/4 5 (?) S89-49-13W 16.78 feet

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 60" long concrete monument w/ brass cap by Griffin destroyed. The base of the monument was intact and I used that to recover the corner position 5 feet north of the E-W 2-track and off the centerline of the road to the north and east. The B. Oak 16" N32W is now 40" N35W, the W. Oak 14 N12E is now a rotted stump and the B. Oak 20" S70E is now 30" S73E. No corner certificate was ever filed prior to this record. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard 1/4 corner on the south line of section 32 of T17N R15W

Monu. 2"x30" stainless steel pipe monument brass disk buried 12" below the surface.

Witnesses:
 W. Oak 20 S14W 47.50'
 W. Oak 18 S35E 87.89'
 R. Pine 7 N49W 7.85'
 Fiberglass Post North 1.4'
 Rebar 1/2" West 11.76'
 R. Pine 5 S71W 42.37'
 W. Oak 28 N42E 123.47'

Peer Group Reviewed and Approved
 Date: 9-10-93
 Kenneth L. Ross
 Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 122

SURVEYOR'S MICHIGAN REGISTRATION NO. _____