

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -- LOCATED IN -- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... 17N N. 15W E. G4
2. PROPERTY CONTROLLING IN SECTION... N. S., R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION... N. S., R. E. W.
4. LOT NO. ... RECORDED PLAT
5. PRIVATE CLAIMS

FILED AT 2 O'CLOCK P M
23 1993
MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 23 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19__ , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1/4 corner common to sections 9 and 10 of T17N R15W
1838 survey by John Hodgson
Set Wood Post
Beech 4 S61W 15 links
Maple 4 N53E 9 links
Undated survey by K.B. Stephens
No monument is mentioned.
Pine 30 N45W 26.5 feet
1972 survey by Robert A. Griffin
Fd. a 1"x30" Pipe
replaced w/ a 5" sq.x 60" long
conc. monu. w/brass cap.
R.Pine 11 S4W 70.00 feet
R.Oak 8 S79W 44.05 feet
Maple 7 N7W 47.22 feet
P.Post 4"x7" South 1.6 feet
1972 survey by Kraft
1" Iron Pipe
R.Pine 11 S3W 70.00 feet
NE 9 NO-50-23W 2638.88 feet
SE 9 SO-29-37E 2608.45 feet
1991 survey by Ken Ross
Fd. conc. monu. by Griffin
NW 10 N00-21-15W 2637.57 feet
SE 10 S00-07-58E 2609.48 feet
Recorded Liber 412 Page 176

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 60" long concrete monument w/ brass cap by Griffin rising 18" above the surface at a fence intersection north and east and 45 feet west of a N-S 2-track and 150 feet north of an E-W 2-track. The 30" Pine by Stephens is still there but badly rotted. Liber 1 Page 213 by Griffin documents the history of this corner. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 corner common to sections 9 and 10 of T17N R15W
Monu. 5" sq. by 60" long concrete monu. with 3" brass disk was left in place.
Witnesses:
B.Oak 5 S60E 38.45'
P.Post 4"x7' South 1.5'
Fence Post 6 North 3.14'
R.Pine 15 S4W 69.94'
R.Oak 14 S77W 44.04'
R.Maple 12 N9W 47.23'

Peer Group Reviewed and Approved
Date: 9-16-93
Kenneth L. Mason, Coun.

SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE



LIBER 3 PAGE 112

SURVEYOR'S MICHIGAN REGISTRATION NO.