

SEP 30 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -: LOCATED IN -: CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... 17N N. 15W E. T. S., R. W.
2. PROPERTY CONTROLLING IN SECTION... N. E. T. S., R. W.
3. MISCELLANEOUS PROPERTY IN SECTION... N. E. T. S., R. W.
4. LOT NO. ... RECORDED PLAT
5. PRIVATE CLAIMS

FILED AT 2 O'CLOCK P M SEP 23 1993 MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram--over) were, in a field survey on August 23 19 93 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to sections 9, 10, 15 and 16 of T17N R15W

1838 survey by John Hodgson Birch 18" for the corner.

1920 survey by C.Landon Monument is not mentioned W.Pine (Stp) 20 S87 1/2E 85 links Tamarack 4 N60W 93 links

1972 survey by Robert A. Griffin Fd. 3/4"x36" Iron Pipe from Blass replaced w/ a 5" sq.x 60" long conc. monu. w/brass cap. P.Post 4"x7' South 1.4 feet W.Pine 22 S88E 101.64 feet Maple 6 S51W 72.47feet W.Pine 18 N57W 70.00 feet

1959 survey by G.Blass Monument is a 3/4"x36" Iron Pipe W.Pine 16 N57W 69.96 feet W.Pine 18 S88E 101.64 feet W.Pine Stp. 38 S78E 99.00 feet P.Pie N6W 69.41 feet

1972 survey by Kraft Fd. Griffin conc. monu. Same witnesses as Blass

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: I found the 5" square by 60" long concrete monument w/ brass cap by Griffin rising 18" above the surface 14.8 feet East of the centerline of an overhead powerline and off the centerline of a 2-track to the North and 29 feet West of the centerline of a 2-track to the Southeast. Landon's 20" Pine stump is gone. The W.Pine 18 S88E 101.64 feet is dead. In 1939 P.Aman (USFS) found the GLO birch stump. He says the GLO calls fit as stated. He took the following 3 witnesses; W.Pine 10 N57-15W 106 links, W.Pine 12 S88-10E 154 links, W.Pine stp. S78-30E 150 links. This documents a clear chain from the GLO to present. Liber 1 Page 214 by Griffin documents the history of this corner. This monument is accepted as a careful and faithful perpetuation of the position of the original corner. A 1993 Survey by Ross of section 10 is recorded in Liber 412 Page 176. Liber 1 Page 246 duplicates Griffin's earlier witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section corner common to sections 9, 10, 15 and 16 of T17N R15W

Monu. 5" sq. by 60" long concrete monu. with 3" brass disk was left in place.

Witnesses:

R.Maple 10 S51W 75.52' P.Post 4"x7' South 1.38' W.Pine 22 N61W 70.08' P.Pole N17W 69.45' W.Pine 10 N74E 105.40'

Peer Group Reviewed and Approved Date: 9-16-93 Kenneth L. Ross Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE



LIBER 3 PAGE 115

SURVEYOR'S MICHIGAN REGISTRATION NO.