

SEP 30 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>17N</u> N. <u>15W</u> E. _____ S., R. _____ W.	1-4
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ E. _____ S., R. _____ W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ E. _____ S., R. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

FILED

AT 2 O'CLOCK P M

SEP 23 1993

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 23 19 93, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1/4 corner common to sections 10 and 11 of T17N R15W**
- | | | |
|---|--|--|
| 1838 survey by John Hodgson
Set Wood Post
Beech 10 N55E 29 links
Beech 12 S71W 30 links | 1991 survey by K. Ross
Fd. 5x60 monu. by Griffin
Witness used were the same
the 1972 witnesses by Griffin | 1972 survey by Robert A. Griffin
Retraced the 1970 survey by Ross
Placed a 5" sq. x 60" long
conc. monu. w/brass cap.
R.Pine 5 N62E 31.55 feet
R.Pine 4 S55E 43.03 feet
W.Oak 8 S86W 43.63 feet
P.Post 4"x7" North 1.7 feet
C1/4 N89-44-14E 2683.00 feet |
| 1901 survey by R.O. Towns
Monument is a wood stake
NW 11 North 39.82 chains
SW 11 South 38.76 chains | 1970 survey by Ken Ross
No monument found
No witnesses taken | |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 60" long concrete monument w/ brass cap by Griffin rising 18" above the surface at a fence intersection N-E-S. Liber 1 Page 221 by Griffin documents the history of this corner. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section corner common to sections 2, 3, 10 and 11 of T17N R15W
Monu. 5" sq. by 60" long concrete monu. with 3" brass disk was left in place.
Witnesses:
R.Pine 10 N64E 31.58'
P.Post 4"x7" North 1.71'
R.Pine 8 S54E 43.02'
W.Oak 11 S88W 43.62'
R.Oak 5 S25W 23.63'

Peer Group Reviewed and Approved
Date: 9-16-93
Kenneth L. Ross
Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 113
SURVEYOR'S MICHIGAN REGISTRATION NO. _____