

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

SEP 30 1993

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	17N N. 15W E. S., R. W.	K11
2. PROPERTY CONTROLLING IN SECTION _____, T. _____	N. E. S., R. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____	N. E. S., R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

FILED

AT 2 O'CLOCK P M

SEP 23 1993

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 23 19 93, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to sections 25, 26, 35 and 36 of T17N R15W

- | | | |
|--|--|---|
| 1838 survey by John Hodgson
Maple 12" for the corner. | 1936 notes of Patterson (USFS)
Monument not found.
A fence line goes east from search area. | 1972 survey by Robert A. Griffin
Set a 5" sq.x 36" long conc. monu.
w/brass cap by testimony.
Maple 4 N61E 65.85 feet
P.Post 4"x7' East 33.05 feet
W.Oak 6 S66E 57.59 feet
R.Oak 5 S56W 52.80 feet
R.Oak 4 S85W 43.53 feet
W1/4 36 South 2593.76 feet
W1/4 25 North 2638.13 feet |
| 1889 survey by Wm. Metcalf
Fd. GLO Maple blown down
Pine Stp. 28 N35 1/2W 95 links
Y.Pine 12 N55 3/4"E 21 links | 1934 survey by C.Lunde
Monument is an Iron Pin & stones
B.Oak 8 N77-15E 29.8 feet
Poplar 8 S88-30W 38.0 feet
W1/4 36 South 2594.2 feet | |
| 1975 survey by K.Ross
Fd. Conc. Monu. by Griffin | | |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
I found the 5" square by 36" long concrete monument w/ brass cap by Griffin buried 48" beneath the surface, 0.5 feet east of centerline in a monument box and off a down fence to the east. This monument was raised with a 1" sq.x14" long spike. All 3 bearing trees by Griffin were destroyed when the county rebuilt this road. Only the leaning P.Post remained. Record dimensions North and South by Lunde confirm this location. In 1935 D.A.Wells (USFS) measured the West line of section 25 at 5393.52 feet and Griffin returned 5384.1 over the same line. Liber 1 Page 224 by Griffin documents the history of this corner. I threw the spike back into the hole atop Griffin's monument. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section corner common to sections 25, 26, 35 and 36 of T17N R15W

- Monu. 5" sq. by 36" long concrete monu. with 3" brass disk was left in place. I raised it to the surface with a 5/8"x24" rebar with stamped aluminum cap in monument box.
- P.Pole N57E 39.45'
 - P.Post 4"x7' East 33'
 - Tw.B.Oak 20x20 S75E 76.66'
 - R.Oak 14 S35E 124.78'
 - Rebar 1/2"x18" West 37.63'
 - N-S Woven Wire Fence East 45.4'
 - Centerline of a 2-track to West is North 320'

Peer Group Reviewed and Approved
Date: 9-16-93
Kenneth L. Ross
Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 119

SURVEYOR'S MICHIGAN REGISTRATION NO. _____