

SEP 30 1993

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. 15W E. _____ S., R. _____ W.	17N	M2
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ S., R. _____ E. _____ W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ S., R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

FILED

AT 2 O'CLOCK P M

SEP 23 1993

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 23 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1/4 corner common to section 1 of T17N R15W and section 6 of T17N R14W**
- | | | |
|---|--|---|
| 1835 survey by Mullett & Brookfield
Set Wood Post
Beech 10 S65W 20 links
Maple 8 N58W 70 links | 1935 field notes of F. Varney (USFS)
Fd. a fence corner east of the corner
w/ fence lines going North and East. | 1972 survey by Robert A. Griffin
Fd. the plow pt. and replaced w/ a
5" sq. x 36" long conc. monu. w/
brass cap.
P. Pole S12E 175.26 feet
B. Oak 7 S46W 91.55 feet
P. Post 4"x7' West 33.12 feet
W. Oak 5 N50W 66.99 feet |
| 1914 survey by George H. Johnson
Plow Point
J. Pine 5 S87 1/2E 61 feet | 1980 survey by Patrick R. Leemon
Fd. conc. monu. by Griffin
NE 1 N0-05-48W 2718.90 feet
SE 1 S0-18-15W 2639.28 feet | |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 36 long concrete monument w/ brass cap by Griffin buried 12" beneath the surface and in the centerline of the N-S road and west of a fence corner with fence lines east and north. Liber 1 Page 229 by Griffin documents the history of this corner. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/4 corner common to section 1 of T17N R15W and section 6 of T17N R14W**
 Monu. 5" sq. by 60" long concrete monu. with 3" brass disk was left in place.
 Witnesses:
 P. Pole N54E 43.47'
 J. Pine 7 S70E 74.40'
 B. Oak 12 S45W 91.64'
 W. Oak 10 N51W 67.01'
 P. Post 4"x7' West 33.05'

Peer Group Reviewed and Approved
 Date: 9-16-93
Kenneth L. Ross
 Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE September 9, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 105

SURVEYOR'S MICHIGAN REGISTRATION NO. _____