

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED
AT 2:35 O'CLOCK P M
OCT 13 1993
MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

For corners in

MASON (County) Located In: Corner Code ##

1. Public Land Survey T 17N R 16W E-5, _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 In Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kenneth L. Ross, in a field survey on OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-5 Section Corner, Secs. 8, 9, 16, & 17
 1838 John Hodgeson set Post
 18" Beech N 71 W 50 lks
 8" Beech S 40 E 70 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 Section Corner, Secs. 8, 9, 16, & 17
 Undated survey by Co. Rd. Comm. took 3 witness
 T. P. NW 61.8'
 P. P. SW 40.0'
 F. Corner South 35.7'
 Ross 1972 Fd 5/8" re-bar riser
 5" Cherry S 01-00 W 24.9'
 P. Pole S 57-30 W 55.5'
 10" Maple N 66-00 W 108.2'
 Ross 1988 Fd 5/8" Iron above 1" Pipe
 P. Pole S 57-30 W 55.5'
 10" Maple N 66 W 108.2'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 Section Corner, Secs. 8, 9, 16, & 17
 Found existing 5/8" Iron rod 6.5' South of center line of Hawley Road, set monument box w/ 5/8" X 24" re-bar with 2 1/2" alum. cap, and is accepted as the best available evidence of the original corner.
 P. Pole S 44 E 43.47'
 P. Pole S 54 W 55.34'
 14" Spruce N 41 W 108.31'
 16" Maple N 62 W 107.94'



Peer Group Reviewed and Approved
 Date: 10-12-93
 Kenneth L. Ross
 Mason County Surveyor

Signed by [Signature] Date 10-12-93
 Surveyor's Michigan License No. 17634