

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MASON (County) Located In: _____ Corner Code # _____

1. Public Land Survey T 17N R 16W G-06
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
 2:53
 MASON COUNTY
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth L. Ross, in a field survey on November 5, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-06 1/4 Corner for Sections 15 and 16, T17N-R16W
 - 1838, John Hodgson, G.L.O. Set Wood Post
 - 1990, Gordon Bonney, RLS #12016 Found Iron in Monument Box
 - #1 Sugar Maple 10" N 62° W 10 lks. 6.60 ft.)
 - #2 Elm 10" S 79° E 21 lks. (13.86 ft.)
 - 1889, W. E. Metcalf show distance at a split on survey, Book 1 Page 215, monument not given
 - 1995, Ken Ross, RLS, #17634 Found Iron in Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-06 1/4 Corner for Sections 15 and 16, T17N-R16W

On November 5, 1997, I Kenneth Ross and Kevin Pritchard (survey tech.) found a 1/2" Re-rod, 24" long, inside an existing monument box, at the center-line of Custer Road (paved). I found no evidence to disputed this location for the corner.


Condition of the recorded witnesses are: #1 Gone #2 Gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-06 1/4 Corner for Sections 15 and 16, T17N-R16W

I replaced, in the exact location, the 1/2" Re-rod with a standard Mason County Monument (5/8" Re-rod, 24" long, with a 2 1/2" aluminum cap) placed inside the existing monument box, and is accepted as a careful and faithful re-establishment of the position of the original corner.

White Cedar	16"	N 25° E	74.32 ft. (P.K. Nail in SE side of tree)
Red Pine	12"	N 40° E	65.20 ft. (P.K. Nail in SE side of tree)
Cherry	9"	S 47° E	52.13 ft. (60d spike in SW side of tree)
Elm	12"	N 87° W	62.00 ft. (60d spike in North side of tree)



Signed by [Signature] Date Nov 5 1997
 Surveyor's Michigan License No. 17634 Peer Review Approved