

MAR 08 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MASON \_\_\_\_\_  
County

Located In: \_\_\_\_\_ Corner Code // \_\_\_\_\_

1. Public Land Survey T 17N R 17W  
T 17N R 17W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John C. Schulke, in a field survey on Sept. 28 and 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-5 Original survey established in 1838 by Hogenson.  
Set a wooden post with the following references:  
Bearing trees: Beech 18" N79°W 22 lks.  
Beech 8" N69°E 42 lks.

In 1876, P. Eastman (County Surveyor) established corner (see Co. Surveyor Record Book 1, pages 32 & 33 in the Mason Co. Register of Deed's Office).

In 1876, P. Eastman (County Surveyor) surveyed Section 16 (see Co. Surveyor Record Book 1, pages 34 & 35 in the Mason Co. Register of Deed's Office).

CONTINUE ON BACK

G-4 Original survey established in 1838 by Hogenson.  
Set a wooden post with the following references:  
Bearing trees: Beech 6" N31°W 4 lks.  
Beech 4" S34°E 38 lks.

In 1876, P. Eastman (County Surveyor) found stone at the corner (see Co. Surveyor Record Book, pages 32 & 33 in the Mason Co. Register of Deed's Office).

In 1877, J.A. Mitchell (Deputy Co. Surveyor) found stone (see Co. Surveyor Record Book 1, pages 46 & 47 in the Mason Co. Register of Deed's Office).

CONTINUE ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 Found 1/2" dia. X 12" iron rebar in monument box. Center line of paved Hawley road is 3 ft. North of iron. Intersection of Stiles and Hawley road. Found culvert to the North 120.5 ft. and a culvert to the East 160 ft.

G-4 Found 1" dia. X 18" iron bar with stone underneath. iron 3.8 ft. West of the center line of paved Stiles road. Intersection of Stiles and Kistler road. Found concrete R/W leaning NW bears N50°E a distance of 48.65 ft. from iron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 Sept. 28, 1993, replaced iron rebar with a 5/8" dia. X 24" rebar with an aluminum County cap stamped to identify the corner. The following corner references:  
power pole #33 S74°E 92.2 ft.  
stop sign N69°E 67.2 ft.  
NE corner of house S58°W 97.04 ft.  
(note: new addition)  
stop sign S75°W 39.61 ft.

G-4 Sept. 29, 1993, replaced 1" X 18" bar with a 5/8" dia. X 24" rebar with an aluminum County cap stamped to identify the corner. The following corner references:  
stop sign N62°E 49.55 ft.  
Power pole S33°E 60.59 ft.  
stop sign S66°W 40.28 ft.  
NE corner of Brick house S54°W 280.92 ft.  
NE corner foundation of house #3947 N09°W 386.42 ft.

FILED

AT 12:15 O'CLOCK P M

OCT 18 1993

MARY GOLDEN KOLASKI  
MASON COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	15		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by John C. Schulke Date Oct 12, 1993  
Surveyor's Michigan License No. RLS-30894

Date: 10-12-93  
Mary Golden Kolaski  
Mason County Register of Deeds

G-5 continued column A:

In 1877, J. A. Mitchell found stone of former survey done by Mr. Eastman (see Co. Surveyor Record Book 1, pages 46 & 47 in the Mason Co. Register of Deed's Office).

In 1880, J.A. Mitchell found stone (see Co. Surveyor Record Book 1, pages 86 & 87 in the Mason Co. Register of Deed's Office).

In 1957, Mason Co. Road Commission shows an 1" shaft in concrete. The following corner references:

power pole	SE	92.5 ft.
NE corner of house	SW	108.5 ft.
Culvert	North	120 ft.
Culvert	East	158 ft.

NOTE: No new references by Mr. Eastman or Mr. Mitchell surveys.

G-4 continued column A:

Not date, Mason Co. Road Commission shows a stone and iron at the corner. The following corner references:

Maple	24"	N40°W	25.4 ft.
Maple	20"	N80°E	90.3 ft.
Maple	20"	S60°W	58.9 ft.

Note: No new references by Mr. Eastman or Mr. Mitchell surveys.